



# SOLAR POWER PLANT PROPOSAL

Prepared for: SRI KRISHNA AGRO DIARY PRODUCT

## Project Summary

| Offer Details |                                 |
|---------------|---------------------------------|
| Offer No.     | REPL/26-27/117                  |
| Issue Date    | 13-04-2026                      |
| Valid Till    | 13-05-2026 (30 days from issue) |

| Customer & Site Specification |                                     |
|-------------------------------|-------------------------------------|
| Customer Name                 | SRI KRISHNA AGRO DIARY PRODUCT      |
| Address                       | Parambua, Chenchua, Hooghly, 712402 |
| Contact Number                | 8509158430                          |
| Email ID                      |                                     |
| State                         | West Bengal                         |
| Roof / Ground Type            | Sheet Roof / Grounded RCC with GI   |
| Project Category              | Commercial                          |
| Electricity Provider          | WBSEDCL                             |
| Monthly Bill                  | ₹ 10000                             |
| Power Factor                  | 0.84                                |

| Solar PV System Specification |                                                            |
|-------------------------------|------------------------------------------------------------|
| System Capacity               | 10 kWp                                                     |
| Module Technology             | Mono-Crystalline Bifacial N-Type Topcon Silicon Technology |
| Inverter Type                 | String Inverter (On-Grid)                                  |
| Panel & Inverter Brand        | UTL / ADANI / VIKRAM / LUMINOUS / SOLIS / TATA             |
| Power Evacuation              | 230 VAC Single Phase                                       |
| Project Type                  | Supply & Install                                           |

## Commercial Offer

| Description | Qty | Base Price | GST @ 5% |
|-------------|-----|------------|----------|
|-------------|-----|------------|----------|



REON ENERGIES PVT LTD

Solar Power | Clean Energy Solutions  
www.reonenergy.in | info@reonenergy.in | 8436649991

Offer No.  
REPL/26-27/117  
Valid for 30 days

|                                                                                                                                                                      |       |            |          |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------------|----------|
| Design, Engineering, Procurement, Construction, Erection,<br>Installation, Commissioning & Testing for <b>10 kWp</b> Solar Power Plant<br>— Commercial (Turnkey EPC) | 1 Set | ₹ 4,60,000 | ₹ 23,000 |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------------|----------|

Total Price Including GST: ₹ 4,83,000 /-

EMI / LOAN FINANCING: Down Payment: ₹ 0 | Loan: ₹ 483,000 | ROI: 7.0% | Tenure: 60 months | Monthly EMI: ₹ 9,564





Energy & Savings Calculation

| Generation & Savings Profile |                      |
|------------------------------|----------------------|
| System Capacity              | 10.0 kWp             |
| Estimated Daily Generation   | ~ 40.0 Units (kWh)   |
| Estimated Yearly Generation  | ~ 14,600 Units (kWh) |
| Assumed Electricity Rate     | ₹ 12.50 / Unit       |
| Estimated Annual Savings     | ₹ 182,500            |

Return on Investment (ROI) & System Life

Payback Period: ~ 2.6 Years  
Expected System Life: 25+ Years  
Post-ROI Savings: 100% Free Electricity & Profit

Loan / EMI Options (7.0% p.a. Reducing Interest)

Calculated on a proposed loan amount of ₹ 483,000.

Option 1: 3 Years Tenure

EMI: ₹ 14,914/month  
Annual EMI: ₹ 178,964  
Net Annual Saving: ₹ 3,536 approx  
Fastest loan closure  
Lowest initial liquidity / profit

Option 2: 4 Years Tenure (Recommended)

EMI: ₹ 11,566/month  
Annual EMI: ₹ 138,792  
Net Annual Saving: ₹ 43,708 approx  
Best balance between EMI & net savings

Option 3: 5 Years Tenure

EMI: ₹ 9,564/month  
Annual EMI: ₹ 114,768  
Net Annual Saving: ₹ 67,732 approx  
Maximum monthly liquidity  
Higher total interest paid over tenure

| Tenure | Monthly EMI | Annual EMI | Net Annual Saving |
|--------|-------------|------------|-------------------|
| 3 Year | ₹ 14.9K     | ₹ 1.79L    | ₹ 3.5K            |
| 4 Year | ₹ 11.6K     | ₹ 1.39L    | ₹ 43.7K           |
| 5 Year | ₹ 9.6K      | ₹ 1.15L    | ₹ 67.7K           |



Products & System Description

A Solar PV power plant converts solar irradiation into electrical energy. The system comprises the following major components:

Technical Bill of Materials (BOM)

| S L | Item                      | Specification                                                    | Qty           | Make / Brand                                   |
|-----|---------------------------|------------------------------------------------------------------|---------------|------------------------------------------------|
| 1   | PV MODULES                | 590Wp Mono-Crystalline Bifacial N-Type Topcon Silicon Technology | 17 Nos.       | UTL / ADANI / VIKRAM / LUMINOUS / SOLIS / TATA |
| 2   | STRING INVERTER           | On-Grid, 1-Phase, Efficiency >98%, IP65                          | 1 No.         | UTL / VIKRAM / LUMINOUS / HAVELLS              |
| 3   | MODULE MOUNTING STRUCTURE | Hot-Dip Galvanised GI, Rooftop / Ground                          | As per Design | AFTR Market / Fabricated                       |
| 4   | SOLAR DC CABLE            | 4 Sq.mm, UV-Protected, TÜV Certified                             | As per Design | Apar Industries / Polycab / KEI                |
| 5   | AC CABLE                  | 1.1kV UV-Protected Aluminium Armoured                            | As per Design | Apar Industries / Polycab / KEI                |
| 6   | MC4 CONNECTORS            | UV-Protected, IP67, DC Rated                                     | As required   | MC4 / Elmex / Phonix / Havells                 |
| 7   | ACDB                      | IP55, MCB Protection, Type-II SPD                                | 1 Set         | Apar Industries / Polycab / KEI                |
| 8   | DCDB                      | IP55, String Fuses, SPD Type-II                                  | 1 Set         | Apar Industries / Polycab / KEI                |
| 9   | EARTHING KIT              | 6 ft Copper Bonded Rod + GI Strip                                | As required   | True Power Ltd / ETP Earthing                  |
| 10  | EARTHING CABLE            | 2.5 Sq.mm Copper, Single Core                                    | As required   | Reputed Make                                   |
| 11  | LIGHTNING ARRESTOR        | ESE Type, Class I+II Protection                                  | As required   | True Power / Nitro / ETP LPS                   |
| 12  | CABLE TRAY & ACCESSORIES  | GI Perforated Tray, ISI Mark                                     | As required   | TATA / JINDAL / SHYAM / JSW                    |



### Scope of Work

- Detailed Solar Power Plant Design & Engineering.
- Supply of all equipment including packaging, forwarding, freight & transit insurance.
- Project Management for smooth execution within the agreed timeline.
- On-site civil works, structural erection and equipment installation.
- Electrical works, cable laying, interconnections, earthing & lightning protection.
- On-site commissioning and performance testing of the complete system.
- Operation & Maintenance training to customer personnel.
- MNRE and CEIG approvals processing (included in proposal scope).

### Notes

- Design is based on standard codes; subject to scrutiny by the owner at their own cost.
- All drawings will be prepared only after receiving the confirmed order and advance payment.
- If site conditions differ from standard design assumptions, the final value may change proportionally.

### Project Execution

The project shall be executed by highly experienced engineers and qualified contractors:

- Preparation of detailed installation and construction documentation.
- Civil works, structural erection and installation of all equipment.
- Electrical interconnections, earthing & lightning protection system.
- Obtaining all required permits, consents and regulatory approvals.
- Commissioning, performance testing and handover with documentation.

### Pre-Commissioning Testing Checklist

| SL | Activity / Test                                                              | Factory | Site | Comm. |
|----|------------------------------------------------------------------------------|---------|------|-------|
| 1  | Solar PV Modules — Visual inspection, IV curve & insulation resistance test  |         |      |       |
| 2  | String Inverter — Factory acceptance test, grid synchronisation verification |         |      |       |
| 3  | Module Mounting Structure — Dimensional, alignment & torque check            |         |      |       |
| 4  | Solar DC Cables & MC4 Connectors — Insulation resistance & polarity test     |         |      |       |
| 5  | AC Cables & ACDB — Continuity, polarity & RCD test                           |         |      |       |
| 6  | DCDB — Fuse rating, SPD operation & isolation test                           |         |      |       |
| 7  | Earthing System — Earth resistance measurement (target < 1 Ω)                |         |      |       |
| 8  | Lightning Protection System — Continuity & bonding verification              |         |      |       |
| 9  | Grid Power Evacuation — Sync relay, anti-islanding & protection trip test    |         |      |       |
| 10 | Surge Protection Devices (SPD) — Functional & leakage current test           |         |      |       |
| 11 | System Performance Ratio — PR > 75% at rated irradiance                      |         |      |       |



Warranty Details

| SL | Component                               | Warranty Period                |
|----|-----------------------------------------|--------------------------------|
| 1  | Solar PV Modules (Product Warranty)     | 12 Years                       |
| 2  | Solar PV Modules (Performance Warranty) | 25 Years                       |
| 3  | String Inverter                         | 5 Years (Extendable to 10 Yrs) |
| 4  | Module Mounting Structure               | 5 Years                        |
| 5  | DC & AC Cables                          | 5 Years                        |
| 6  | ACDB / DCDB                             | 1 Year                         |
| 7  | All Other Parts & Workmanship           | 1 Year                         |

Delivery & Completion Schedule

- Material delivery: 1–2 weeks from receipt of Purchase Order and advance payment.
- Installation, testing & commissioning: 1–3 weeks from first material delivery at site.
- Final handover, O&M; training and documentation: within 1 week of commissioning.

Payment Terms

1. Down Payment of ₹ 0 at the time of Purchase Order/Agreement signing.
2. Loan Amount of ₹ 483,000 successfully arranged and sanctioned.
3. Monthly EMI stands at ₹ 9,564 for a tenure of 60 months at 7.0% ROI.
4. EMI cycle starts based on bank/NBFC disbursement terms post commissioning.

Validity of Offer

This proposal is valid for 30 days from the date of issue.

General Terms & Conditions

Approvals:

MNRE and CEIG approvals are included. Any other government or third-party approval is in the client's scope.

Confidentiality:

All information exchanged between the parties in connection with this proposal shall be maintained strictly confidential.

Taxes, Duties & Rates:

GST @ 5% applicable on solar system installation as per prevailing government norms. Any future change in taxes/duties shall be payable by the customer.

Force Majeure:

Neither party shall be liable for delays caused by circumstances beyond reasonable control — acts of God, government orders, or natural calamities.

Dispute Resolution:

Any dispute shall first be resolved through mutual negotiation; failing which, through arbitration under the Indian Arbitration Act, jurisdiction: Hooghly, West Bengal.

Assumptions & Customer Scope



- Module Mounting Structures designed to suit the customer's specific roof/ground conditions.
- Power evacuation at 230V (single phase) or 415V (three phase); tapping point in existing panel is in customer's scope.
- Indoor/sheltered space for inverter, control panels and metering equipment is in customer's scope.
- Distance between ACDB and existing evacuation point assumed  $\leq 50$  metres.
- Construction power and potable water to be provided by the client at no cost.
- Sand, cement and stone chips required for civil/cable-laying works are in customer's scope.
- Tree trimming or shadow-removal works (if required for shadow-free area) are in customer's scope.
- Panel cleaning is not in REON's scope — customer to clean panels at least twice per week.
- This is a turnkey project; unused/surplus materials will be returned to REON inventory on completion.





### Major Clients of Reon Energies Pvt Ltd

We have successfully executed solar projects for leading organisations across West Bengal and India.

### Recent On-Grid Projects in Nearby Locations

| SL | Project Details                             | Capacity |
|----|---------------------------------------------|----------|
| 1  | Ramakrishna Mission Shilpapitha, Belgharia  | 52 kW    |
| 2  | Ecos Housing Project, New Town              | 26 kW    |
| 3  | Metalist Consultant Pvt. Ltd., New Town     | 8 kW     |
| 4  | Electro Steel Castings Limited, Khardha     | 35 kW    |
| 5  | Bankura Medical College & Hospital          | 10 kW    |
| 6  | Times of India Building, Salt Lake Sector-5 | 40 kW    |
| 7  | Agrico Industries, Howrah                   | 40 kW    |
| 8  | Mali Agri Tech Pvt. Ltd., Ranaghat          | 80 kW    |
| 9  | Nicco Park, Salt Lake-5 / New Town          | 125 kW   |
| 10 | M/s Allen Laboratories Limited, Kolkata     | 160 kW   |
| 11 | G. K. Plastics Pvt. Ltd., Bandel            | 160 kW   |
| 12 | Apollo Gleneagles Hospitals, EM Bypass      | 325 kW   |
| 13 | Oscar Equipments Pvt. Ltd., Bishnupur       | 500 kW   |
| 14 | Kamala Industries, Sangur                   | 700 kW   |
| 15 | Century Ply Boards India Ltd.               | 1,500 kW |

Bank Details

Account Name: REON ENERGIES PRIVATE LIMITED

Bank A/C No: 01622021000021274

IFSC: PUNB0016220

Branch: Singur

Bank Name: Punjab National Bank

GST Details

Registration Number: 19AAPCR6346E1ZY

Contact Details

Phone: +91 8436649991

Email: info@reonenergy.in

Website: reonenergy.in

| For: REON ENERGIES PVT LTD | For: SRI KRISHNA AGRO DIARY PRODUCT |
|----------------------------|-------------------------------------|
| Authorised Signatory       | Customer Acceptance                 |